ENGINEERING DEPARTMENT.

ELECTRICAL DEPARTMENT.

Notification dated 19th September 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Chief Electrical Engineer, Bangalore, up to 2 P.M. on 27th October 1930 for constructing a block of Operator's quarters with a unit of latrine at Tumkur Town.

1. The tenders will be opened in public at 2 P. M., on 27th October 1930. The work should be completed within three months and the monthly progress should not be less than Rs. 1,000.

2. The plans, detailed estimates and the conditions may be seen at the Chief Electrical Engineer's Office, Bangalore, on all working days during the office working hours.

3 Tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed. The rates should be in figures as well as in words.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or in Government Promissory Notes, as earnest money and be superscribed " Tenders for constructing a block of Operator's quarters with a unit of latrine at Tumkur Town " in default of which, tenders will be rejected.

5. Final acceptance of any tender will rest with the Chief Electrical Engineer, who does not bind himself to accept the lowest or any tender or to assign any resson whatever for the rejection of any tender. The Chief Electrical Engineer also reserves the right to accept or reject any portion of the tender.

6. Within eight days of the award of the tender, the successful tenderer will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful tenderer will be posted on the Notice Board in the Chief Electrical Engineer's Office, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The construction work should be started within a week from the date of the notification of the acceptance.

10. Any other conditions that the contractor may wish to state should also be included in his tender.

11. Water for construction should be got at the contractor's own expense.

12. Specifications for works are those recognised by the Mysore Public Works Department and Marryot's specifications.

13. The contractor should be bound by the conditions of the Schedule of Contract of the Electrical Department.

Statement showing the approximate quantities for constructing a block of Operators' Quarters with a unit of latrine at Tumkur Town.

Serial No.	Items of work	Per	Quantity	Rates in	
				Figures	Words
1	Earthwork excavation for foundations including filling in basement.	C.yd.	52	Rs. a. p.	
2a	Concrete stone jelly in mortar foundation ...	C.ft.	553		
b	Stone in mortar foundation and basement including through stones at 6'-0" centre to centre in every course.	"	875		
c	Burnt brick in clay superstructure ...	"	2,628		
d	Stone slabs 4" thick roughly dressed and fixed complete.	S.ft.	159		
e	Stone slabs 6" thick exposed parts finely dressed and set in mortar.	"	14		
f	Chunam plastering 2 coats ...	Sqr.	54·75		
g	Chunam pointing with thread lines ...	"	1·50		
h	White and colour washing 2 coats ...	"	56·25		
i	Constructing sinks with drain pipes etc., complete.	Each	4		
j	Providing mortar and pestle ...	No.	2		
k	Chunam patty or border over roof ...	R.ft.	82		
3	Flooring with 3" concrete stone jelly in chunam mortar flooring with chunam plaster and a floating coat of	Sqr.	7·55		

Serial No.	Items of work	Per	Quantity	Rate	
				In figures	In words
				Rs. a. p.	
4*a*	Roofing with 1st class Mangalore tiles on teak wood reepers and cement pointed.	Sqr.	12·30		
b	Roofing with 24 B. W. G. Galvd. Iron corrogated iron sheeting with G. I. screws, washers etc., complete.	„	1·26		
c	Ridge tiles set in mortar and cement pointed	R.ft.	30		
d	Ventilating tiles set in mortar and cement pointed.	Each	8		
5*a*	Matty wood work wrought and put up with 2 coats of wood oiling complete.	C ft.	43·26		
b	Honney wood battened door 1" thick shutters with hinges, bolts, etc, fittings complete including tarring to frames. etc.	S ft.	264		
c	Honney wood windows battened with 1" thick shutters and iron bars 5/8" diam. including all fittings complete.	„	72		
d	Honney wood ventilators	„	36		
e	Chacolate painting 2 coats	Sqr.	9·25		
f	Honney wood planks for shelves 1" thick with teakwood pegs fixed complete including tarring.	S.ft.	45		
g	Galvanized iron sheet sunshades with T. W. frame including painting, etc.	No.	8		
h	Teak wood eave board plain 9" x 1" thick ..	R.ft.	60		
	Constructing 1 Unit of Latrine attached to Block No. 5 Tumkur Town.				
1	Earthwork excavation and filling in etc. ...	C.yd.	4		
2*a*	Stone in mortar foundation and basement ...	C.ft.	130		
b	Burnt brick in mortar superstructure ...	„	196		
c	Chunam plastering	Sqr.	4·91		
d	Chunam pointing	„	0·56		
e	White and colour washing	„	5·47		
f	Cement plastering ½" thick.	„	0·80		
g	Tarring two coats	„	0·63		
3	Flooring with 3" concrete and cement plaster ½" thick on top.	„	0·38		
4	Providing galvd. iron sheet tubs 12" x 6" x 6" with handles, etc., complete with tarring.	No.	6		

Notification dated 27th September 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Chief Electrical Engineer, Bangalore, up to 2 P.M., on 31st October 1930, for constructing a block of two Operators' quarters at Dodballapur Town.

1. The tenders will be opened in public at 2 P.M. on 31st October 1930. The work should be completed within three months and the monthly progress should be not less than Rs. 1,000.

2. The plans, detailed estimates and the conditions may be seen at the Chief Electrical Engineer's Office, Bangalore, on all working days during the office working hours.

3. Tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed. The rates should be in figures as well as in words.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes as earnest money, and be superscribed "Tenders for constructing a block of two Operators' quarters at Dodballapur Town," in default of which, tenders will be rejected.

5. Final acceptance of any tender will rest with the Chief Electrical Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender. The Chief Electrical Engineer also reserves the right to accept or reject any portion of the tender.

6. Within eight days of the award of the tender, the successful tenderer will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful tenderer will be posted on the Notice Board in the Chief Electrical Engineer's Office, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The construction work should be started within a week from the date of the notification of the acceptance.

10. Water for construction should be got at the contractor's own expense.

11. Specifications for works are those recognised by the Mysore Public Works Department and Marryot's specifications.

12. The contractor should be bound by the conditions of the schedule of contract of the Electrical Department.

Construction of a block of Operators' Quarters to accommodate two families at Doddaballapur:—

Serial No.	Items of work	Unit	Quantity	Rates
				Rs.
1	Earthwork excavation and filling in basement ...	C.yd.	51	
2(a)	Stone jelly in chunam mortar concrete foundations ...	C.ft.	583	
(b)	Stone in clay, foundation and basement ...	"	1,055	
(c)	Burnt brick in clay, superstructure	"	3,058	
(d)	Stone slabs 5" thick, roughly dressed and set in mortar	"	217	
(e)	Do 4" thick do do	"	24	
(f)	Chunam plastering two coats	Sqr.	61·87	
(g)	Chunam pointing	"	2·10	
(h)	Binding wall 1-1/8' x 9" brick in clay and chunam plastering.	R.ft.	50	
(i)	Plain cornice, 6" projection	"	50	
(j)	Constructing sinks complete	Each	5	
(k)	Providing mortar and pestle	"	2	
3	Flooring with 3" lime concrete and chunam plastering with a floating coat of cement.	Sqr.	8·79	
4(a)	Roofing with First Class Mangalore tiles on teak reepers 2" x 1" complete.	"	11·24	
(b)	Ridge tiles set in mortar and cement pointed ...	R.ft.	41	
(c)	Cuddapah slab terrace with Cuddapah slabs 1½" thick, 3" concrete and plastering on top complete.	Sqr.	3·20	
(d)	Burnt brick in mortar 9" projection	R.ft.	63	
(e)	Burnt brick in mortar parapet wall 1½' high as per plan.	"	59	
(a)	Matty wood work wrought and put up with two coats of wood oiling.	C.ft.	35·28	
(b)	Doors with teak frames and honey wood battened shutters 1" thick with iron fixtures.	S.ft.	240·50	
5(c)	Windows with teakwood frames and honey wood battened shutters 1" thick and iron bars 5/8" diameter complete.	S.ft.	96	
(d)	Honney wood planks 1" thick for shelves fixed on teakwood pegs complete.	"	48	
(e)	Chacolate painting two coats	Sqr.	12·18	
(f)	Expanded metal 3" x 1½" x 1/8" mesh fixed on teak wood frames complete.	S.ft.	·75	
6(a)	Rolled steel girders fixed complete (Continental) ...	Cwt.	18·45	
(b)	Rain water down pipes 3" diameter fixed complete ...	R.ft.	20	

Abstract Notification.

Attention of the public is hereby invited to the detailed Notification dated 15th September 1930, calling for tenders for constructing an Office and Stores Building in Seringapatam Town published in Part VI, pages 1166 and 1167, of the *Mysore Gazette*, dated 25th September 1930. The last date for receiving tenders is 2 P.M., on 13th October 1930.

C. M. CARIAPA,
Chief Electrical Engineer.

KOLAR DIVISION.

Notice dated 26th September 1930.

The attention of the public is invited to the Notification published in the *Mysore Gazette*, Part VI, page 1170, dated 25th September 1930, calling for tenders for widening and revetting the well in the Government Silk Farm at Kolar Taluk.

The latest date for tender is 18th October 1930.

Notice.

The attention of the public is invited to the Notification published in the *Mysore Gazette*, Part VI, page 1167 to 1168, dated 25th September 1930, calling for tenders for restoring Halesomerasanahalli tank, Kolar Taluk.

The latest date for tender is 4th October 1930.

Notice.

The attention of the public is invited to the Notification published in the *Mysore Gazette*, Part VI, pages 1168 to 1169, dated 25th September 1930, calling for tenders for restoring Siddaghatta tank, Mulbagal Taluk.

The latest date for tender is 18th October 1930.

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

MYSORE RAILWAYS.

MYSORE DIVISION (OPEN LINES).

Notification dated 27th September 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Open Line Division, Mysore Railways, Mysore, upto 2 P.M., on Saturday the 18th October 1930, from contractors, who are willing to do the work of construction of 1-12 feet Girder Bridge across the Railway line for the Irwin Canal, Maddur Branch at Mile 260/3-4.

2. Every tender must be accompanied by an earnest money of Rs. 100, which can be paid to the Auditor, Mysore Railways, Mysore, and the receipt thereof enclosed along with the tender.

3. Tenders should be submitted in special forms, which can be obtained from the Executive Engineer, Mysore Railways, Mysore, on payment of rupee one.

4. Tenders which give rates, as per estimate rates, or so much per cent above or below estimate rates, will not be considered.

5. The name of the accepted tenderer will be posted on the Notice Board of the Executive Engineer's Office. No enquiries regarding the acceptance or rejection of a tender will be replied.

6. The earnest money of the unsuccessful tenderers will be returned as soon as possible after the tenders are disposed of.

7. The successful tenderer should deposit 5 per cent of the value of work, not exceeding Rs. 500, and execute within a week from the date of notification of acceptance of his tender, the usual Railway Schedule Agreement. Failure to comply with this condition will render the tenderer liable for forfeiture of the earnest money and contract cancelled.

8. The final acceptance of the tender will rest with the Engineer-in-Chief, Mysore Railways, Mysore, who does not bind himself to accept the lowest or any tender and who further reserves to himself the right to reject, without assigning any reasons therefor, any or all the tenders.

9. Work should be started within two weeks from the date of acceptance of tender, and completed, in three months with a guaranteed monthly rate of progress. The accompanying schedule gives the approximate quantity of works and this quantity is not guaranteed.

10. The time limit specified in para 9 should be strictly adhered to and any violation of this will render the contractor liable to forfeit his 5 per cent deposit amount not as a penalty but as ascertained and liquidated damages recoverable accordingly.

11. Plans and specifications and other details of work to be done are available for inspection in the Executive Engineer's Office, Mysore Railways, Mysore, where intending tenderers may call and obtain required information during office hours.